Estimate for Extending the two wings of Lakshmipuram, Boys' Middle School, Mysore.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavation for foundation and filling in basement	C.yds.	..	52	
2	Granite stone jelly in chunam concrete with tamping and consolidation	C.ft.	..	469	
3	Burnt Brick in chunam mortar for foundation and basement	„	..	1,794	
4	Burnt Brick in mortar superstructure ..	„	..	342	
5	Burnt Brick in mud superstructure	„	..	1,482	
6	Burnt stone slabs dressed and fixed in mortar ..	S.ft.	..	337	
7	Chunam plastering and rounding the corners ..	Sqrs.	..	41·12	
8	White and colour washing	„	..	41·12	
9	Teakwood panelled doors $1\frac{1}{2}''$ thick shutters with iron fittings, etc., complete	S.ft.	..	49	
10	Teakwood panelled windows $1\frac{1}{2}''$ thick with iron bars $\frac{3}{4}''$ dia. and iron fittings, etc., complete..	„	..	135	
11	Teakwood ventilators with iron bars and glazed shutters, etc., complete	S.ft.	..	54	
12	Teakwood wrought and put up	C.ft.	..	110·20	
13	Cut stone pillars with base and capitals and two line dressing	No.	..	6	
14	Roofing with 1st Class Mangalore pattern Yelahanka tiles on teak reepers $1'' \times 2''$, etc., complete	Sqrs.	..	15·63	
15	Ridge tiles set in mortar and pointed ..	R.ft.	..	50	
16	Cornice over gables and corners	„	..	144	
17	Teakwood eave board $9'' \times \frac{3}{4}''$ ornamental as per existing one	„	..	114	
18	Flooring with square tiles on 3" chunam concrete and cement pointing, etc.	Sqr.	..	9·32	
19	Painting with two coats of Shalimar (wood coat) chocolate paint	„	..	17·21	

S. RAMASWAMY,
Assistant Engineer.

MYSORE DIVISION.

Notification dated 20th October 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 2 P.M., on 9th November 1936, (Monday) for Restoring Alur tank, Register No. 234, Maddur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred and thirty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Alur tank, Register No. 234, Maddur Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for restoring Alur Tank, Register No. 234, Maddur Taluk.

No.	Items of work	Per	Rate	Quantity	Cost
	R. L. OF BUND.	Unit	Rs. a. p.		Rs.
1	Jungle clearing	Grade	0 8 0	21	11
2	Cutting steps and grips in old bund	,,	1 0 0	21	21
3	Earthwork to bund with consolidation ..	C.yd.	0 4 6	4,416	1,242
4	Old stone work	,,	0 12 0	88	66
5	New stone work	,,	1 12 0	551	964
6	Gravelling to the slopes and top including carting and tamping	,,	0 8 0	498	249
7	New grade stones including cutting figures and painting, etc., ...	Each	2 4 0	23	52
8	Providing and fixing Index stones ..	,,	0 6 0	23	9
9	Providing and fixing Register No. and date stones including figuring and painting, etc., complete	,,	5 0 0	1	5
10	Do do B. M. Stone ..	,,	3 0 0	2	6
11	Do do Gauge stone ..	,,	10 0 0	1	10
	SLUICE No. 1 BETWEEN C. S. No. 5 & 6.				
1					
2	Earth work excavation	C.yd.	0 3 0	65	12
3	Concrete in surki mortar (of stone jelly) ..	C.ft.	0 4 6	104	29
4	Burnt brick in surki mortar	C.yd.	0 5 0	359	112
5	Burnt stone slabs 6" thick dressed and fixed ..	S.ft.	0 7 6	62	29
6	Plastering with surki mortar..	Sqr.	3 12 0	0.98	4
7	Cutting holes in upper and lower orifice slab and over gibbed wall and guide slabs, etc., ..	Each	0 8 0	4	2
8	Cast iron pipes 6" diameter, Railway charges cart hire and fixing, etc., complete ..	R.ft.	3 0 0	30	90
9	Jally wood plug and iron rods 1" diameter and locking arrangements	Each	15 0 0	1	15
	Earthwork refilling with consolidation ..	C.yd.	0 1 6	30	3
	SLUICE No. 2 AT C. S. No. 9				
1	Earthwork excavation	C.yd.	0 3 0	85	16
2	Stone jelly concrete in surki mortar	C.ft.	0 4 6	104	29
3	Burnt brick in surki mortar	,,	0 5 0	359	112
4	Stone slabs 6" thick dressed and fixed ..	S.ft.	0 7 6	62	29
5	Plastering with surki mortar..	Sqr.	3 12 0	0.98	4
6	Cutting holes in slab	Each	0 8 0	4	2
7	Cast fron pipes 6" diameter including Railway charges and cart hire and fixing, etc., complete	R.ft.	3 0 0	27	81
8	Jally wood plug and iron rod 1" diameter and Locking arrangements, etc., complete ..	Each	15 0 0	1	15
9	Earth work refilling with consolidation ..	C.yd.	0 1 6	42	4

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	EXTENDING THE LEFT WASTE WEIR 72' AND INCREASING THE WEIR CREST FROM R. L. 50·00 TO 51.00.				
1	Earth work	C.yd.	0 3 0	266	49
2	Stone jelly concrete in surki mortar	C.ft.	0 4 6	290	82
3	Removing top layer of old masonary to raise new brick work	,,	0 0 6	122	4
4	Burnt brick in surki mortar	,,	0 5 0	883	276
5	Plastering with surki mortar..	Sqr.	3 12 0	9.33	35
6	Burnt stone slabs 6" thick dressed and fixed ..	S.ft.	0 7 6	401	189
7	Rough stone work for apron	C.yd.	1 12 0	147	257
8	Resetting old stone work ..	,,	0 12 0	31	23
9	Jelly wedging to old apron	S.yd.	0 5 0	114	36
10	Providing joggle joints on coping slab ..	Each	0 12 0	13	10
10a	Providing surki mortar concrete at the junction of body wall and apron	L. S.	..	..	22

Notification dated 20th October 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 2 P.M., on 29th November 1936, (Monday) for Improving the Right Sluice Channel of Thagadur Kommanakere, Nanjangud Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.—

4. Each tenders must be accompanied by a deposit of Rupees two hundred and ten only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Improving the Right Sluice Channel of Thagadur Kommanakere, Nanjangud Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for improving the Right Sluice Channel of Thagadur Kommanakere tank, Nanjangud Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	1. REGULATION.—*Constructing a new cistern for the rear of sluice with dividing notches.*				
1	Earth work excavation	C.yd.	0 3 0	13	2
2	Surki concrete filling foundation and cistern plateform	C.ft.	0 4 0	97	24
3	Burnt bick in surki mortar for basement and superstructure	„	0 5 0	145	45
4	Burnt stone slabs 6″ thick dressed	S.ft.	0 7 0	86	38
5	Surki mortar plastering with cement rendering	Sqr.	4 8 0	1·64	7
6	Teak wood sluice shutters 1½″ thick plank with iron fittings, etc.	S.ft.	3 0 0	3	9
7	New rough stone wings for channel	C.ft.	1 14 0	7	13
8	Iron rod 4′ long with gearing rod and Locking arrangement complete	No.	7 8 0	2	15
	DISTRIBUTION.—*A. Improving the existing channel.*				
1	Earth work cutting and black cotton soil ..	C.yd.	0 2 6	2443	382
2	Cutting in rocky soil mixed with soft rock ..	C.yd.	0 6 0	1108	416
3	Earth work banking with watering and tamping	„	0 4 0	1653	413
4	Turfing the slopes of bund in bank portion ..	S.yd.	0 1 0	1979	124
5	Providing new mile stone	No.	6 0 0	1	6
6	Providing grade stones at every 220′	„	1 8 0	24	35
	B. Constructing a Dwarf wall.				
1	Earth work excavation	C.yd.	0 3 0	23	4
2	Surki concrete for foundation	C.ft.	0 4 0	27	7
3	Burnt brick in surki mortar	„	0 5 0	54	17
4	Surki plastering with cement rendering ..	Sqr.	4 8 0	·25	1
5	New rough stone wings	C.yd.	1 14 0	16	30
6	Surki mortar grouting	Sqr.	2 0 0	·81	2
7	Burnt stone slabs 6″ thick dressed and fixed in surki mortar, over drop wall	S.ft.	0 7 0	12	5
	C. Constructing a new Cast Iron Madavoy.				
1	Earth work excavation	C.yd.	0 3 0	15	3
2	Surki concrete for foundation	C.ft.	0 4 0	75	19
3	Burnt brick in surki mortar	C.ft.	0 5 0	134	42
4	Surki plastering with cement rendering ..	Sqr.	4 8 0	·99	4
	D. Cost of pipes for sluices.				
1	Cost of iron pipes 12′ long 8″ 500 weights 2 qrs. 15 lbs.	..	..	..	..
	9″ 6 cwts. 2 qrs. 5 lbs.	..	..	..	..
	8″ 1 1 27	..	..	..	..
	4″ 2 0 3	..	..	..	..
	7″ 4 2 8	C.ft.	8 0 0	21	175
	Cement concrete madavoys for 12 feet length (all cement concrete madavoys similar to that of Kempasagara Tank)	R.ft.	..	..	..

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	III. COMMUNICATION.—*Constructing a new Cart Bridge.*				
1	Earth work excavation	C.yd.	0 3 0	21	4
2	Surki concrete foundation	C.ft.	0 4 0	75	19
3	Burnt brick in surki mortar, basement ..	,,	0 5 0	192	60
4	Burnt stone slabs 6″ thick	,,	0 7 0	84	37
5	Surki plastering with cement rendering ...	Sqr.	4 8 0	48	2
6	Rough stone wings for channels	C.yd.	1 14 0	12	22
	IV. CROSS DRAINAGE WORKS.				
	A. Constructing a new super passage.				
1	Earth work excavation in gravelly soil ..	C.yd.	0 4 0	116	29
2	Surki concrete for filling foundation	C.ft.	0 4 0	1,292	323
3	Burnt brick in surki mortar	,,	0 5 0	708	221
4	Surki plastering with cement rendering ..	Sqr.	4 8 0	11·28	51
5	Burnt stone slabs 6″ thick, Covering slabs ..	S.ft.	0 7 0	351	154
6	New rough stone revetment	S.ft.	1 14 0	238	446
7	Earth work to bank	C.yd.	0 4 0	648	162
8	Turfing slopes of the bank	S.yd.	0 1 0	1,111	69
	Repairs to existing aqueduct and relieving weirs.				
1	Repairing the aqueduct by closing leaks ..	No.	50 0 0	1	50
2	Repairs to relieving weirs with apron of rough stone work, etc.	No.	15 0 0	5	75

Notification dated 20th October 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 2 P.M. of 9th November 1936 (Monday), for constructing a Rural Type Dispensary at Ravandur, Hunsur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred and fifty only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Rural Type Dispensary at Ravandur, Hunsur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate of the probable cost of constructing a Local Fund Dispensary of Rural Type at Ravandur, Hunsur Taluk.

No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earth work excavation for foundation and filling in basement	C.yd.	0 4 0	65	16
2	Granite stone jelly concrete in chunam mortar .	C.ft.	0 3 6	605	132
3	New size stone in clay in foundation and basement, including through bond stones at 6′ intervals and corner stones	C.ft.	0 4 0	1,294	324
4	Superstructure burnt brick in mud	,,	0 3 6	1,068	233
5	Do do do in mortar ..	,,	0 4 6	545	153
6	Burnt stone slabs 6″ dressed and fixed ..	S.ft.	0 7 0	283	124
7a.	Providing and fixing T. W. panelled windows with 3/4″ diameter iron bars with hinges, etc., complete, with silicate painting 2 coats on both sides including stoppers	,,	2 0 0	81	162
b	Do do 1/2 windows ..	,,	1 8 0	9	14
8	Providing and fixing T. W. panelled door with hinges, bolts, etc., complete without sill piece, including 2 coats of silicate painting with stoppers	S.ft.	1 14 0	184	345
9	T. W. Ventilators with glazed shutters with horizontal iron bar including silicate painting	,,	1 4 0	24	30
10	T. W. Shelves with frame (horizontal) planks inside, shutters panelled, hinges, bolts, hooks, stoppers, etc., complete including silicate painting	,,	1 8 0	68	102
11	Cut stone pillars or R. C. Pillars with base capital complete 4 pillars (8½ to 9″ wide)	No.	15 0 0	4	75
	Do do half pillar ..	,,	7 8 0	2	
12	I Girder for verandah bressummers including dog bolts, nails, etc., complete	C.wt.	12 0 0	6·83	82
13	T. W. wrought and put up with two coats of wood oiling complete	C.ft.	5 0 0	105·77	529
14	Madras terrace for verandah as per specification	Sqr.	35 0 0	2·34	81
15	First Class Mangalore tiled roofing on T. W. reepers with wood oiling for reepers complete	Sqr.	30 0 0	11·24	337
16	Flooring with cement over a bed of 3″ lime concrete, 1½″ cement concrete, coloured and lines cut to have tiled-like appearance ..	,,	25 0 0	7·42	186
17	Ridge tiles set in cement including hips ..	R.ft.	0 8 0	78	39
18	Chunam plastering 2 coats in squares ..	Sqr.	3 4 0	32·73	106
19	White washing two coats	,,	0 4 0	32·73	8
20	Cement pointing to basement	,,	4 0 0	2·66	11
21	Eave Board of plain design (9″ deep) ..	R.ft.	0 10 0	150	94
22a	Teak wood Finials	No.	1 8 0	2	3
b	Teak wood pendents	No.	0 10 0	6	4
23	Cement plastering to step parapets	Sqr.	9 0 0	0·18	2
24	Parapet wall over front verandah including plastering, white-washing complete	C.ft.	0 10 0	46	29
25	Providing sink 3′ ×3′ in compoundings ..	L. S.	..	..	5
26	Providing and fixing chamber to the front window in compounding	,,	..	..	5
27	Providing and fixing T. W. cantilevers in walls and placing T. W. planks in compounding and stores including tarring	,,	..	..	50
28	Providing and fixing T. W. plain design screen with a door, for the prescribing room for purposes of examination in private ..	,,	..	..	50
29	Making holes in sill-slabs of doors to seat, door bolts	,,	..	..	4
30	Down water pipes from the verandah roof ..	,,	..	..	5
31	Mortar bonds for the tiled roof	,,	..	..	20

Abstract estimate for the probable cost of constructing a Kitchen.

No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation foundation in gravelly soil	C.yd.	0 4 0	9	3
2	Granite stone jelly concrete in chunam mortar	C.ft.	0 3 6	100	22
3	Size stone in clay with bond stones ..	,,	0 4 0	173	43
4	Burnt brick in mud	,,	0 3 6	330	72
5	Providing and fixing burnt stone slabs 6″ thick dressed and fixed	S.ft.	0 8 0	24	12
6	Teakwood work wrought and put up ..	C.ft.	5 0 0	10·38	51
7	Providing and fixing T. W. Ornamental eave board	S.ft.	0 8 0	63	32
8	Providing and fixing T. W. panelled door including chacolate painting, etc.	S.ft.	1 12 0	18	32
9	Do ventilators	,,	1 8 0	4½	7
10	Roofing with 1st Class Mangalore tiles over teak reepers	Sqr.	30 0 0	2·29	69
11	Providing and fixing ridge tiles set in mortar ..	R.ft.	0 8 0	15¼	8
12	Plastering with chunam mortar	Sqr.	3 8 0	6·19	22
13	Cement pointing	,,	4 0 0	·45	2
14	Flooring with Vajragare	,,	12 0 0	·70	9
15	Providing bath room, etc., complete	L. S.	..	..	5

Abstract estimate of the probable cost of constructing a Latrine.

No.	Items of work	Per	Rate	Quantity	Cost
			Rs. as. p.		Rs.
1	Earthwork excavation in gravelly soil ..	C.yd.	0 4 0	5	1
2	Size stone in mortar filling	C.ft.	0 6 0	132	50
3	Burnt brick in mortar	,,	0 5 0	280	87
4	Constructing ovans for seats with burnt brick in mortar with cement plaster, etc. ..	No.	1 0 0	6	6
5	Cement plaster	Sqr.	9 0 0	5·53	50
6	Flooring with 3″ stone jelly concrete and ½″ cement plaster above it	,,	16 0 0	·30	5
7	Inserting pipes with cement	L. S.		..	4
8	Constructing cisterns (2)	,,	..	..	10
9	Constructing step, earthwork, brick in mortar .	,,	..	..	5
10	Burnt brick in mortar coping including plastering	R. ft.	0 6 0	48	18

V. V. PATANKAR,
Executive Engineer.

MEDICAL DEPARTMENT

THE EPIDEMIC DISEASES HOSPITAL AND LEPER ASYLUM, BANGALORE.

Abstract Notification dated 9th October 1936.

The attention of the public is invited to the detailed notification calling for tenders for the supply of diet and other articles to the Epidemic Diseases Hospital and Leper Asylum, Bangalore, from 1st January 1937 to 31st December 1937 (both days inclusive), published in pages 1698-1700 of Part VI of *Mysore Gazette*, dated 15th October 1936.

T. SUBBA RAO,
Medical Officer.